
# AUTOMATIC LIGHT CONTROL SYSTEM DOES NOT OPERATE

#### **WIRING DIAGRAM**



#### INSPECTION PROCEDURE

### 1 CHECK LIGHT


(a) Check that tail light and head light light up.

NG

FLOW CHART(GO TO FLOW CHART OF HEAD LIGHT OR TAIL LIGHT)

OK

## 2 INSPECT HEADLAMP DIMMER SWITCH ASSY(AUTO)



- (a) Inspect light control switch continuity.
  - (1) Check that there is continuity between terminals at each switch position as shown in the chart.


Switch operation	Tester connection	Specified condition
OFF	<ul> <li>No continuity</li> </ul>	
AUTO	12 – 16	Continuity

NG)

REPLACE HEADLAMP DIMMER SWITCH ASSY

OK

#### 3 CHECK AUTOMATIC LIGHT CONTROL SENSOR



- (a) Check the continuity between terminal 3 (+) and body ground as shown in the chart below.
- (b) Measure voltage between terminals as shown in the chart below.
- (c) Using an oscilloscope, check that signal waveform appears between terminals.

#### Standard:

Terminal No. (Symbol)	Tester connection	Condition	Specified condition
1 (CLTB)	1 – 3	Constant	10 – 14 V
3 (CLTE)	3 – Body ground	Constant	Continuity
4 (CLTS)	4 – 3	IG SW ON Dimmer SW AUTO	Signal waveform appears depending on outside brightness

ок 🖯

FLOW CHART(GO TO FLOW CHART OF HEAD LIGHT OR TAIL LIGHT)

- 4 CHECK HARNESS AND CONNECTOR(BETWEEN INSTRUMENT PANEL J/B ASSY AND AUTOMATIC LIGHT CONTROL SENSOR)
- (a) Check that signal waveform appears between terminal B7 17 (CLTS) and body ground. **Standard: Bar appears.**

ок

CHECK AND REPLACE INSTRUMENT PANEL JUNCTION BLOCK ASSY

NG

- 5 CHECK HARNESS AND CONNECTOR(BETWEEN INSTRUMENT PANEL J/B ASSY AND AUTOMATIC LIGHT CONTROL SENSOR)
- (a) Measure voltage between terminal B7 15 (CLTB) and body ground.

Standard: 10 - 14 V

ок

CHECK AND REPLACE INSTRUMENT PANEL JUNCTION BLOCK ASSY

NG

- 6 CHECK HARNESS AND CONNECTOR(BETWEEN INSTRUMENT PANEL J/B ASSY AND AUTOMATIC LIGHT CONTROL SENSOR)
- (a) Check the continuity between terminal B7 16 (CLTE) of instrument panel J/B and 3 (CLTE) of automatic light control sensor.

Standard: There is continuity.

OK

CHECK AND REPLACE INSTRUMENT PANEL JUNCTION BLOCK ASSY

NG

REPLACE AUTOMATIC LIGHT CONTROL SENSOR